

# SURVEY FOR KEITH L. HASSLER

LOCATED IN THE S.E. 1/4 OF SEC. 19, T. 37S. R. 1W, W.M.  
MEDFORD, OREGON  
JUNE 1, 1982

DIVINITY  
SQUARE SUB.

FD. BR. DISK IN CONC.  
INITIAL POINT

FD. 5/8" IRON  
PIN FLUSH  
W.C. FILED  
SURVEY NO. 1857

N 0° 21' 30" W  
55.90'

S 89° 59' 30" W 95.00'  
S 50° 21' E 4.00'

HASSLER

N.E. COR. INST.  
#74-10381, O.R.

215.166'  
N 0° 21' 30" W 355.49'  
(REC. = N 0° 21' 40" W 355.43')

WABASH AVENUE

STEVENS ST.

FD. 3/4" IRON PIPE 5" DEEP.  
5/16" COB. TO SECTIONS 19 & 20  
PER C.S. ESTABLISHMENT 1950.

BASIS OF BEARING:  
FILED SURVEY #1857



SCALE 1" = 60'

LEGEND:

- SET 5/8" x 24" REBAR WITH RED PLASTIC CAP STAMPED "BOYDEN R.L.S. 281"
- FOUND MONUMENT AS INDICATED.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Mark E. Boyden*

OREGON  
NOV. 9, 1951  
MARK E. BOYDEN  
281

SURVEY BY:  
BOYDEN SURVEYORS  
108 MISTLETOE ST.  
MEDFORD, OREGON.

\*\* RECEIVED \*\*

Date 6/9 By SK

This survey consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY  
SURVEYOR

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Keith L. Hassler  
1326 Bonita  
Medford, Oregon

BY: Boyden Surveyors  
108 Mistletoe  
Medford, Oregon

PURPOSE: To monument the corners on the Northerly boundary of tracts described in Instrument Nos. 78-09553 and 78-14094, less 78-14093 of the Official Records of Jackson County, Oregon, being located in the Southeast Quarter of Section 19, Township 37 South, Range 1 West of the Willamette Meridian.

PROCEDURE: The calls of the tracts described in Instrument No. 66-01177 O.R. and in Instrument No. 74-10381, O.R. were coordinated with the data from Filed Survey No. 1857 to determine the beginning point of the Hassler property. Monuments found shown were utilized to establish the necessary survey controls. Survey was executed with E.D.M. equipment.

Basis of Bearings is Filed Survey No. 1857.

May 25, 1982

