



REGISTERED
PROFESSIONAL
LAND SURVEYOR
Larry J. Friar
OREGON
JULY 16, 1971
LARRY J. FRIAR
961

**** RECEIVED ****
Date 9/2/82 By SK
This survey consists of:
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

- LEGEND:**
- ⊙ = FD. ORIG. GOV'T SURVEY CORNER PER CO. SURVEYOR'S RE-ESTABLISHMENT NOTES.
 - = FD. 5/8" IRON PIN
 - = SET 5/8" IRON PIN WITH PLASTIC CAP STAMPED FRIAR PLS 961

**MAP OF SURVEY
FOR
K.Y.J.C. RADIO STATION**

LOCATED IN THE N.W. 1/4 SEC. 1, T37S, R1W
W.M., JACKSON CO. OREGON
SCALE: 1" = 200' AUGUST, 1982
BASIS OF BEARING: POLARIS OBSERVATION.
PREPARED BY: FRIAR-MOFFIT & ASSOC.
MEDFORD, OREGON.

SURVEY NO. 9390

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: KYJC Radio Station
1840 Barnett Road
Medford, OR 97501

LOCATION: NW 1/4, Section 1, T37S, R1W,
WM, Jackson Co., Oregon

PURPOSE: To monument corners of parcel
shown on the annexed map, which
was being purchased by the
client.

PROCEDURE: Located and measured to the four
corners of the NW one-quarter
(1/4) of Section 1, then frac-
tionized the quarter by the pro-
portional method.

The center one-quarter (1/4)
corner and the 5/8" pin 30.00
feet South of the center North
one-sixteenth (1/16) corner as
established by Survey No. 2048
and Suvey No. 2188 were accepted
as being in the proper location
by this survey.

Measurements were made with E.D.M.
device and theodolite.

Corners found and set are as
shown on the annexed map.

The exact right-of-way lines of
Dry Creek Road were not determined
because of the difficulty in
recovering the old County center-
line traverse points.

The fence on the North side of the
road was accepted as being the
correct location of the county
right-of-way.

DATE: September 1, 1982

FRIAR-MOFFIT & ASSOCIATES
717 West 10, Suite 1
Medford, OR 97501
Phone: 772-2782

