

** RECEIVED **

Date 9/24 By SK

This survey Consists of:

1 sheet(s) Map

2 page(s) Narrative

JACKSON COUNTY
SURVEYOR

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Russell D Hendricks

OREGON
July 9, 1965
RUSSELL D. HENDRICKS
688

Survey No. 9402 Page 2 of 2

T. 38S. R. 2E.
 $\frac{1}{4}$ $\frac{29}{32}$
 C.S.
 1969

From which:

An 8" White Oak brs. N35 $\frac{1}{2}$ ⁰W 32.3ft. Face healed.
 An 8" White Oak brs. S16 $\frac{1}{2}$ ⁰E 38.8 ft. Scribing visible.
 Distances to lower face.

CORNERS SET

Section Corner common to Sections 29, 30, 31, and 32 - I set a 1 $\frac{1}{4}$ " x 36" iron pipe with a 2 $\frac{1}{2}$ " brass cap exposed 13" and marked

LS 688
 T38S
 R2E

30	29
31	32

1982

From which:

An 18" White Oak brs. N58⁰E 134.31 ft. Scribed "S29" "BT"
 A 10" White Oak brs. S76⁰E 59.69 ft. Scribed "S32" "BT"
 A 13" White Oak brs. N46⁰W 26.84 ft. Scribed "S30" "BT"
 A 5/8" x 28" rebar with plastic cap set flush with the ground brs.
 S45⁰W 15.0 ft.

CN 1/16 Corner Section 30 - I set a 3/4" x 36" iron pipe with a 2 $\frac{1}{2}$ " brass cap exposed 18" and marked

LS 688
 CN 1/16

•
 S30
 1982

From which:

An 8" Black Oak brs. N08⁰E 62.78 ft. Scribed "CN 1/16 S30" "BT"
 A 7" White Oak brs. S31 $\frac{1}{2}$ ⁰W 17.71 ft. Scribed "CN 1/16 S30" "BT"

C-E-NE 1/64 Corner Section 30 - I set a 1 $\frac{1}{4}$ " x 36" iron pipe with a 2 $\frac{1}{2}$ " brass cap exposed 12" and marked

LS 688
 C E NE 1/64

•
 S30
 1982

From which:

A 16" Black Oak brs. S153/4⁰E 63.57 ft. Scribed "C-E-NE 1/64 S30" "BT"
 An 8" White Oak brs. N72⁰W 45.50 ft. Scribed "C-E-NE 1/64 S30" "BT"

Found possible post set in Lovejoy's unrecorded survey of 1955 S42⁰E 16.25 ft. from corner. Post had been disturbed and was lying on the ground

SURVEY NARRATIVE TO COMPLY WITH
OREGON REVISED STATUTES 209.250

Survey for: Robert C. Jenkins
83933 Cloud Nine Road
Florence, Oregon 97439

Location: Section 30, Township 38 South, Range 2 East of the Willamette Meridian.

Basis of Bearings: County Survey File No. 9259

Purpose: To monument property corners

Procedure: Original survey work retraced by this project was done in two contracts; the West line of Section 30 by Ives and Hyde in 1854 and all other lines by D.P. Thompson in 1858. Lovejoy did work in 1955 (unrecorded survey from Hoffbuhr's files). L. Friar set the E-E 1/64 corner between Sections 19 and 30 in 1976 (County File No. 6435). Swain set the Section corner common to Sections 31, 32, 5, and 6 (County File No. 4719). The Jackson County Surveyor has remonumented several original corners.

A closed traverse was run tying the found corners and a search was made for missing corners based on proportional positions and using county search notes. Corners were then set using the Bureau of Land Management's Manual of Surveying Instructions.

Fences in this section are not consistent with property lines.

CORNERS FOUND AND ACCEPTED FOR CONTROL

All B.T. measurements are to the center of the tree at the lower face unless noted.

Section Corner common to Sections 19, 24, 25, and 30	See County File No. 9244
--	--------------------------

1/4 Corner common to Sections 19 and 30	See County File No. 9393
E-E 1/64 Corner common to Sections 19 and 30	
Section Corner common to Sections 19, 20, 29, and 30	

N 1/16 Corner common to Sections 25 and 30	See County File No. 9372
1/4 Corner common to Sections 25 and 30	
Section Corner common to Sections 25, 30, 31, and 36	

Section Corner common to Sections 31, 32, 5, and 6	See County File No. 9159
--	--------------------------

1/4 Corner common to Sections 29 and 32 - At this corner I found a 2 1/2" brass cap exposed 12" and marked