

Section Corner on Range Line to Sections 1 and 12, Township 34 South,  
 Range 1 East, and Sections 6 and 7, Township 34 South, Range 2 East,  
 Willamette Meridian

Purpose: To mark new bearing trees to perpetuate Corner.

Found a 2" pipe exposed 8 inches with a galvanized Cap marked S1 S6  
 MEDCO  
 S12 S7

A 10½ inch dia. Fir N 28° W 20.4 ft. unopened  
 A 9 inch dia. Fir stump cut off at ground level  
 S 65½° E 32.6 ft.

New Trees. Measurements are to the center of tree at the stump.  
 I nailed a 1¼ inch dia. Brass washer marked <sup>LS</sup>1086 to the lower face  
 of each tree.

Basis of bearing is the Northeast bearing tree of 1955 Jackson Co.  
 Re-establishment of Corner.

An 8 inch dia. Cedar S 86½° W 6.8 ft. marked S12 BT  
 A 5 inch dia. Cedar S 53½° E 12.0 ft. marked S 7 BT  
 A 5½ inch dia. Fir N 82° E 7.8 ft. marked S 6 BT

