

SURVEY NARRATIVE TO COMPLY WITH
PARAGRAPH 209.250 OREGON REVISED STATUTES


SURVEY FOR: Rogue River National Forest
P. O. Box 520
Medford, Oregon 97501

LOCATION: One-quarter common to Sections 10 and 11, Township
33 South, Range 1 West, Willamette Meridian,
Jackson County, Oregon.

BASIS OF BEARING: Solar observation

PURPOSE: To preserve and protect evidence found at the one-
quarter corner common to Sections 10 and 11.

PROCEDURE: At the corner point I found a standard General Land
Office 1-inch diameter iron post with a 2 1/2-inch
diameter brass cap marked:



From which the following references:

A 19-inch diameter fir snag, 12 feet high, bears S 50° 02' W, 70.2 feet distance with a single healed blaze.

A 16-inch diameter fir bears N 80° 51' E, 6.4 feet distance with a single healed blaze.

I mark the following new reference:

A 10-inch diameter fir bears S 43° 34' W, 27.9 feet distance, scribed 1/4 S10 LS 1071 BT.

January 19, 1983

HAROLD L. CENTER
Registered Professional Land Surveyor
Oregon Certificate No. 1071

