



FD. B.L.M. BRASS CAP  
MARKING THE W. 1/4  
CORNER SECTION 19.

N87°49'47"W  
2318.03'

FD. 1" PIPE WITH EXPANDER  
MARKING THE N. 1/4 COR.  
SECTION 19.

N00°01'31"E  
1336.25'

N87°49'47"W

1323.89' 1323.89'

FD. 1" PIPE WITH EXPANDER  
MARKING THE E. 1/4 COR.  
SECTION 19.

N00°01'31"E  
2622.64'

FD. COUNTY SURVEYOR'S  
BRONZE CAP MARKING THE  
S. 1/4 CORNER SECTION 19.

RECEIVED \*\*  
Date 5/25/83 By SK  
This survey consists of:  
/ plat map  
/ narrative  
COUNTY SURVEYOR

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Lloyd R. Moffit*

OREGON  
JULY 17, 1970  
LOYD R. MOFFIT  
944

LEGEND:

- = FOUND MONUMENT AS SHOWN.
- = SET 5/8" IRON PIN WITH PLASTIC CAP STAMPED, MOFFIT PLS 944.
- = BLAZED TREES AND TAGGED PROPERTY LINE.

BASIS OF BEARINGS:  
SURVEY NO. 1369.

PLAT OF SURVEY  
FOR

**TIMBER PRODUCTS COMPANY**

BEING A PORTION OF SECTION 19,  
TOWNSHIP 32 SOUTH, RANGE 2 EAST, W.M.  
JACKSON CO. SCALE: 1" = 100'  
OREGON DATE: MAY, 1983

PREPARED BY: FRIAR-MOFFIT AND ASSOCIATES  
MEDFORD, OREGON

SURVEY NO. 9624

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: Timber Products Company  
P.O. Box 1669  
Medford, OR 97501

LOCATION: A portion of Section 19, Township 32 South,  
Range 2 East, Willamette Meridian, Jackson  
County, Oregon.

PURPOSE: To survey, mark and monument property lines  
as instructed by Timber Products Company.

PROCEDURE: Closed traverses were run to all four one-  
quarter (1/4) section corners. The Timber  
Products Company property lines were then  
marked with a combination of blazed and  
painted trees, and aluminum tags marked  
TP P/L.

I set the following corners and scribe trees  
as follows:

At the center one-quarter (1/4) corner I  
set a 5/8" x 30" iron pin from which;

A 14" Fir bears N 66° E 23.3 feet,  
scribed C1/4 S19, BT.  
A 10" Pine bears S 46° E 7.6 feet,  
scribed C1/4 S19, BT.

At the center East one-sixteenth (1/16)  
corner I set a 5/8" x 30" iron pin from  
which;

A 8" Fir bears S 37° E 19.5 feet,  
scribed CE 1/16 S19, BT.  
A 18" Fir bears S 72° W 32.9 feet,  
scribed CE 1/16 S19, BT.

At the center North one-sixteenth (1/16)  
corner I set a 5/8" x 30" iron pin from  
which;

A 14" fir bears S 11° E 30.0 feet,  
scribed CN 1/16 S19, BT  
A 8" Oak bears S 83° 13' W 30.6 feet,  
scribed CN 1/16 S19, BT.

Distances to bearing trees were measured to  
the center of the tree at the BT scribe.

DATE: May, 1983

FRIAR-MOFFIT & ASSOCIATES  
717 West 10th, Suite 1  
Medford, OR 97501  
Phone: 503-772-2782

\*\* RECEIVED \*\*  
Date 5/25/83 By SK  
This survey Consists of:  
1 sheet(s) Map  
1 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Lloyd R. Moffit*  
OREGON  
JULY 17, 1970  
LOYD R. MOFFIT  
944