



SCALE 1" = 200'
 Basis of Bearings R.S. No. 5621
 O = Set 5/8"x24" Pin (tagged RLS 638)
 ● = Found mon. as noted

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
George Burrell
 OREGON
 JULY 10, 1964
 GEORGE W. BURRELL
 S.P.

*** RECEIVED ***
 Date 5/24/83 By SK
 This survey consists of:
1 sheet(s) Map
1 page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

MAP OF SURVEY
 Located in Section 14, Twp 38S, R2W
 For: JEFFERY KENDLE and C.R. YONAKA
 By: George Burrell, Land Surveyor
 May 18, 1983

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250FOR:

Jeffery Kendle
4844 Dark Hollow Rd.
Medford, Oregon

and

C.R. Yonaka
P.O. Box 961
Medford, Oregon

LOCATION: Section 14, Twp. 38 S, R 2 W

PURPOSE: To monument the corners and mark the boundary lines of the Kendle and Yonaka ownerships according to deed record.

PROCEEDURE: The exterior sectional corners of control were traversed to, from which the true subdivisional lines were determined as shown on the accompanying map.
The 2" iron pipe set for the proportional N.W. section corner by R.S. No. 5621 appears to have been destroyed by construction of a pond. The position of this corner was determined from the found 5/8" iron pin R.P. of said survey.
The 1" iron pipe found at the S.E. corner of section 14, was held as the true corner after an evaluation of the following evidence:

1. The course and distance to the 1/4 corners to the North and West as determined by my survey, are within the limits of error expected of the original Gov. survey.
2. The course and distance to the 1/4 corners to the South and East as reported by recorded surveys no. 3227 and 6415 are also within the normal error expected.
3. From the 1" iron pipe, the partial stump remains of a Black Oak approx. 20" in dia. with two dead and down sucker growth trunks approx. 5" in dia., bears S 18° W 10.6 feet.

No evidence was found for the original North and West 1/4 corners of section 14. Accordingly, these positions were calculated but not monumented.

With the subdivisional data thus determined, the Kendle and Yonaka properties were monumented according to deed record.

BY: George Burrell, Land Surveyor
1379 Brookdale
Medford, Oregon 97501

May 23, 1983

