



** RECEIVED **
 Date 6/6/83 By LR
 This survey consists of:
 1 sheet(s) Map
 1 page(s) Narrative
 JACKSON COUNTY SURVEYOR

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
 LARRY J. FRIAR
 961

SURVEY NO. 9629

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: Hugh W. Gardner
5955 Hillcrest
Medford, Oregon 97501

LOCATION: West one-half (1/2) of Section 24, Township
37 South, Range 1 West, Willamette Meridian,
Jackson County, Oregon.

PURPOSE: To survey and monument the boundaries of
the client's property prior to creating
"Gardner Subdivision."

PROCEDURE: All of the exterior corners of Section 24
and corner monuments from previous filed
surveys necessary to determine the boundary
of the property were tied in by traverse
using an electronic total station.

Using the information obtained the fractional
subdivision of Section 24 was computed and
it was found that the monuments set by
Survey No. 2790 and subsequent Survey No.
6360 were too far out of position to be
acceptable. New monuments were set in the
correct position as shown on the annexed
map.

The location of Roxy Ann Road was determined
by holding the two found pipes at the point
of intersection of the centerline tangents
as shown by Survey No. 557 and Survey No.
2872 and using the record curve data.

DATE: May 24, 1983.

FRIAR-MOFFIT & ASSOCIATES
717 West 10th, Suite 1
Medford, OR 97501
Phone: 503-772-2782

