

SURVEY NO. 9676

SURVEY NARRATIVE TO COMPLY WITH ORS 209.250

DATE: July 25, 1983

SURVEY FOR: City of Medford and Sage Pipelines Co.
Public Works Dept. P. O. Box 4707
Medford, Oregon 97501 Medford, Oregon 97501

LOCATION: Section 16, Township 37 South, Range 1 West of
the Willamette Meridian, Jackson County, Oregon



PURPOSE: To remonument the southeast corner of Lot 3,
Block 3, Foothill Subdivision, Jackson County,
Oregon and to monument the Northwest corner of
the tract of land described in Instrument No.
74-06246 of the official Records of Jackson
County, Oregon

PROCEDURE: Used the 5/8 inch pins and 1/4 corner common
to sections 16 and 21 found in Lone Pine Road
as control and the bearings and distances
indicated on the Foothill Subdivision plat
to remonument the southeast corner of Lot 3,
Block 3 of Foothill Subdivision

To monument the Northwest corner of the tract
of land described in Instrument No. 74-06246,
the West line of Lot 16 of Stewart Acres as
established on the Foothill Subdivision plat
was used to establish the East-West position
of the Northwest corner and the North line
of that tract of land described in Volume 353
Page 326 of the Deed Records of Jackson County
as established on the Foothill Subdivision
plat was used to establish the North-South
position of the Northwest corner

BASIS OF BEARINGS: Foothill Subdivision Plat

SURVEYOR'S NAME AND ADDRESS: Keith A. Smith
Kas & Associates
1609 S. Whitman
Medford, Oregon 97501



Keith A. Smith

