

SURVEY NO. 9713

SURVEY NARRATIVE

Survey for: P & M Cedar Products
c/o Bub Meek
P.O. Box 2396
White City, Or 97503

Survey by: Edward A. McGinty, R.S.
P.O. Box 1531
Medford, Or 97501
June, 1983

Basis of Bearing: Survey No. 5856

Location: SE 1/4 of Sec. 19, NE 1/4 of Sec. 30, T36S, R1W.

Purpose:

To resurvey, at the request of client, the line abutting Gregory Rd. and to relocate a line 50 ft. being easterly of the center of the Medco rail road line. The retracement includes only Gregory Road and a line shown as South 20° 06' 32" West, 465.94 ft. and then a redraft of the previous survey No. 5856. By observation and pacing, found other monuments. These monuments were not verified by an actual resurvey. No attempt was made of validity adverse possession of the fence line and of possible shed encroachment.

Survey No. 9366 and 9356 center line alignment of the Medco railroad is in conflict with previous survey by 0.58' at Gregory Rd. and is identical to previous survey, by this firm, further southwesterly.

It is apparent that by extending survey No. 9366 it would not agree with previous survey of records near the 1/4 cor. between Sec. 19 and 20

