



FD. 1" I. PIPE W/ STAMPED EXPANDER
TOP, "SW COR NW NE 1/16 COR,
C.S. 1959", 2 B.T.'S, B.T. SNAG.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Robert M. Thompson
OREGON
JANUARY 1983

NOTES:

BEARING BASIS = PORTION OF LINE SHOWN, PER SURVEY NO. 5161.

SEE NARRATIVE FOR CORNER DETAILS.

x—x FENCES.

LINE SHOWN IS MARKED W/ RED-PAINTED BLAZES, RED FLAGGING, 1/2"X5" "P/L BCC" ALUM. TAGS.

THIS SURVEY & MAP WAS COMPLETED FOR THE EXCLUSIVE USE OF BOISE CASCADE CORP.

FD. 5/8" I. ROD, SURV. NO. 5161,
ALSO FD. 2" I. PIPE.

FD. 1" I. PIPE W/STAMPED EXPANDER,
"CTR. 1/4 SEC 27, C.S. 1959", 3 B.T.'S,
B.T. STUMP.

FD. 1" I. PIPE W/STAMPED EXPANDER
"SW COR. NW NW SE C.S 1959", 3 B.T.'S.



** RECEIVED **
Date 11/8/83 By SK
This survey consists of:
 sheets' Map
 narrative
JANUARY 1983
SURVEY

SURVEY TO RETRACE & MARK LINE BETWEEN COUNTY SURVEYOR "INTERMEDIATE CORNERS" IN SW 1/4 NE 1/4, NW 1/4 SE 1/4 SEC. 27, T 32S, R 3E, W.M., JACKSON CO., OREGON.

NOVEMBER 4, 1983 SCALE: 1 INCH = 200 FEET
ROBT. M. THOMPSON & ASSOC., 1140 ACACIA LANE
GRANTS PASS, ORE. 97527.

SURVEY TO RETRACE & MARK LINE BETWEEN COUNTY
 SURVEYOR "INTERMEDIATE CORNERS" IN SW $\frac{1}{4}$ NE $\frac{1}{4}$, NW $\frac{1}{4}$ SE $\frac{1}{4}$,
 SECTION 27, T32S, R3E, W.M.
 JACKSON CO., OREGON

November 4, 1983

Narrative description to comply with Par. 209.250, O.R.S.
 (Note: 1 map sheet accompanies this narrative)

BY: Robert M. Thompson & Assoc., 1140 Acacia Lane, Grants Pass, OR 97527

FOR: Boise Cascade Corp., Timber & Wood Prod. Group, P.O. Box 100, Medford, OR 97501

PURPOSE: As stated above.

Procedure:

Information was obtained from the Jackson County Surveyor's files, of "Intermediate Corners" set for the County by C.Z. Boyden, Deputy County Surveyor, for monuments set or perpetuated in 1929 and 1959. A portion of the subject line was also surveyed by Survey No. 5161, and used for bearing basis. My survey ran a traverse between the monuments found, shown on my map. The line between the County Surveyor-set monuments was then computed, and marked on the ground as shown on my map. County Surveyor monuments found are as follows, meas. to original faces of bearing trees:

- 1) Found 1" I. Pipe w/stamped expander top, "SW Cor. NW $\frac{1}{4}$ NE $\frac{1}{4}$ 1/16 cor., C.S. 1959, and B.T.'s:
 16" D. Fir N 50 $\frac{1}{2}$ °W 28.5', healed faces.
 17" W. Fir S 80°E 65.9', healed faces.
 14" W. Fir snag N 33°E 7.1', scribe vis., 1929.
 (At cor. of fences, westerly and southerly.)
- 2) Found 1" I. Pipe w/stamped expander top, "Ctr. $\frac{1}{4}$ Sec. 27 C.S. 1959", and B.T.'s:
 25" D. Fir N 20 $\frac{1}{2}$ °E 34.2' scribe part vis., 1929.
 21" W. Fir N 47°E 58.6', healed faces.
 30" D. Fir stump S 12°E 59.5', healed face.
 (At cor. of fences northerly, southerly, westerly.)
- 3) Found 1" I. Pipe w/stamped expander 4" down, mkd. "SW cor. NW $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$, C.S. 1959", and B.T.'s:
 33" Pine N 50 $\frac{1}{2}$ °E 25.8' scribe vis., 1929.
 36" Cork Elm S 32 $\frac{1}{2}$ °W 128.1', scribe vis., 1929.
 18" I. Cedar N 27°E 51.9', healed faces, nearly behind a 26" Pine.
 (Mon. is under corral fence, N 58°W, S 58°E)

