

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250.

SURVEY FOR:

MARTY AND JESSIE GEISZLER

462 SECOND ST.

GOLD HILL, OR. 97525

LOCATION:

THE SOUTH ONE-HALF (1/2) OF THE NORTH ONE-HALF (1/2) OF THE SOUTHEAST ONE-QUARTER (1/4) OF THE SOUTHWEST ONE-QUARTER (1/4) OF SECTION 35, TOWNSHIP 36 SOUTH, RANGE 3 WEST, WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON.

PURPOSE:

TO SURVEY AND SET THE CORNERS OF THE

CLIENT'S PROPERTY.

PROCEDURE:

THE NORTHWEST CORNER OF SECTION 35 HAS BEEN DESTROYED FOR MANY YEARS. IT IS IN A FIELD WHICH HAS BEEN PLOWED MANY TIMES OVER THE PAST YEARS. THE NEAREST SECTION CORNER TO THE NORTH IS TWO MILES NORTH. HOWEVER, THE SOUTH LINE OF D.L.C. NO. 38, WHICH WAS SURVEYED WITHIN A YEAR OF THE SECTION LINES, IS LESS THAN ONE-QUARTER MILE NORTH. WHEN SAID SOUTH LINE WAS SURVEYED, A TIE WAS MADE TO THE SECTION LINE AND TO THE NORTHWEST CORNER OF SAID SECTION 35. THEREFORE SAID SOUTH LINE OF D.L.C. NO. 38 WAS USED TO DETERMINE THE NORTHING OF THE NORTHWEST CORNER OF SECTION 35.

A SEARCH WAS MADE FOR THE NORTH ONE-QUARTER CORNER OF SECTION 35, BUT NO ORIGINAL EVIDENCE COULD BE FOUND. THERE IS A ONE STRAND BARBED WIRE FENCE RUNNING SOUTH AND EAST FROM A POINT NEAR SAID ONE-QUARTER (1/4) SECTION CORNER.

A SEARCH WAS MADE FOR THE EAST ONE-QUARTER (1/4) CORNER OF SECTION 35 AS SET DURING SURVEY 3684. FLAGGING WAS FOUND ON THE FENCE NEAR WHERE THE CORNER SHOULD HAVE BEEN BUT NO EVIDENCE OF THE CORNER COULD BE FOUND. SHRUBBERY IS NOW PLANTED ALONG SAID FENCE. THE CORNER WAS MOST LIKELY DESTROYED WHEN SAID PLANTING OCCURRED.

THE SOUTH ONE-QUARTER (1/4) SECTION CORNER IS IN A CREEK BOTTOM. IT WAS TOLD TO ME BY THE OWNER OF THE PROPERTY TO THE NORTH-WEST OF SAID CORNER THAT THE ONE-QUARTER (1/4) CORNER AND THE BEARING TREES WERE DESTROYED 25 YEARS AGO BY THE PEOPLE WHO OWNED THE PROPERTY TO THE EAST OF SAID CORNER.

SINCE SOME OF THE PROPERTY OWNERS IN THIS AREA HAVE BEEN KNOWN TO PACK GUNS AND SHOOT AT PEOPLE, A WITNESS CORNER WAS SET IN THE

MARTY AND JESSIE GEISZLER PAGE 2 DECEMBER, 1983

COUNTY ROAD RIGHT-OF-WAY INSTEAD OF SETTING THE ACTUAL ONE-QUARTER (1/4) SECTION CORNER.

A SEARCH WAS ALSO MADE FOR THE WEST ONE-QUARTER (1/4) SECTION CORNER. I FOUND TWO OAK TREES IN THE GENERAL AREA OF THE CORNER WHICH HAD BEEN OPENED UP IN THE PAST. NO EVIDENCE OF SCRIBING COULD BE FOUND IN EITHER TREE.

A TRAVERSE WAS RAN AROUND SECTION 35 WITH EDM EQUIPMENT WITH A CLOSURE EXCEEDING 1:40,000.

CORNERS WERE THEN SET AS SHOWN ON THE ATTACHED MAP. THE PIN SET AT THE NORTHWEST CORNER OF SECTION 35 IS BURIED 0.8 FEET AND HAS ROCKS AND BROKEN CONCRETE BLOCKS AROUND IT. IT ALSO HAS A FENCE POST DRIVEN IN THE GROUND CLOSE TO THE CORNER. THE 5/8 INCH PIN SET DURING SURVEY NO. 6416 BEARS NORTH 65° 10' 13" EAST 6.81 FEET.

DATED:

DECEMBER 1983 83-163

FRIAR-MOFFIT & ASSOCIATES

* * RECEIVED * *

Date 1/4/84 By SK

This survey Consists of:

______ sheet(s) Map

______ page(s) Narrative

JACKSON COUNTY
SURVEYOR

PROFESSIONAL LAND SURVEYOR

Saya Z. W. J. J.

OREGON
LOYD R. MOFFIT

REGISTERED