



REGISTERED
PROFESSIONAL
 LAND SURVEYOR

Edward A. McGinty 12/21/83

OREGON
 1983
 EDWARD A. MCGINTY
 331

SURVEY IN NE 1/4 SEC. 21, T.36S., R.4W., WM.
FOR
JACKSON CO. et-al

BY EDWARD A. MCGINTY
 COURT HOUSE
 MEDFORD OREGON

JACKSON CO. SURVEYOR
 SCALE 1" = 50'
 ● = Fd 5/8" I. PIN
 ○ = Fd 3/4" Pipe
 ○ = Set 5/8" x 30" Rebar

**** RECEIVED ****
 Date 1/10/84 By SK
 This survey consists of:
 — 1 sheet(s) Map
 — 1 page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

SURVEY NO. 9827

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Jackson County Parks & Recreation
Jackson County Courthouse
Medford, Oregon 97501

BY: Edward A. McGinty
Jackson County Surveyor

DATE: December 21, 1983

LOCATION: Northeast quarter of Section 21, Township 36 South,
Range 4 West, W.M.

BASIS OF BEARING:
South line of Highway 99 as shown on Survey Nos. 1855
and 6846.

PROCEDURE:

The purpose of this survey was to establish a line for a boundary line agreement between Charles Schlumpberger and a County owned parcel. The purpose of showing the extension of right of way lines from survey nos. 1855 and 6846 is for drafting purpose only. The alignment as shown has commonly been accepted by local surveyors and closely agrees with the improvements.

Monument found, as shown on the southerly line of Highway, are 5/8 iron pins approximately 4 ins. deep.

The Northwest corner of Donation Land Claim 39; found a 2 ins. brass disk, marked and described according to official records.

At point "A", found a deed record corner being a 3/4 ins. iron pipe approximately 15 ins. deep. (Reference; see D.R. Vol. 216, Pg. 386).

Chord "B" was computed after running deed record to a theoretical point and adjusted to right of way now shown.

Monuments set being 5/8 ins. iron pins, 30 ins. long, set approximately flush with the ground.

