

9832

Office 476-2425

MAX H. HULL Land Surveying

231 N. W. 'B' Street Grants Pass, Oregon 97526

SURVEY NARRATIVE to comply with Paragraph 209.250, O.R.S.

DATE: December 15, 1983

FOR: Robert Denman
1629 Slagle Creek Rd.
Grants Pass, OR

PURPOSE: To set the West 1/16 corner and determine the approximate location of the East line of the Northwest Quarter of the Northwest Quarter of Section 4, Township 38 South, Range 4 West of the Willamette Meridian, Jackson County, Oregon. Also to locate an existing driveway crossing said Northwest Quarter of the Northwest Quarter.

PROCEDURE: Beginning at the Northwest corner of said Section 4, at which point I found a 1965 B.L.M. brass cap from which I found:

- A Black Oak 32" diameter, South 80° West 182 links
- A Fir 9" diameter, North 58° East 60 links
- A White Oak 8" diameter, South 75° East 134 links
- A Madrone 22" diameter, South 73° West 69 links
- A Fir 15" diameter, North 54° West 46 links

Thence I traversed North 89°43'00" East 2662.08 feet to the North Quarter corner, at which point I found a 1980 County Surveyor brass cap from which I found:

- A Madrone stump 12" diameter, South 2° East 10.0 feet
- A Fir 7" diameter, North 20°10' East 26.15 feet
- A White Oak 6" diameter, South 70° East 41.16 feet

Thence I computed and set the West 1/16 corner and marked the approximate East line of said Northwest Quarter of the Northwest Quarter; thence I surveyed the existing driveways as shown on the map.

Meridian is based on the G.L.O. Survey of the North line of said Section 4.

