

0986

MAP OF SURVEY

LOCATED IN

S.E. 1/4 OF SEC. 20 T.34 S., R.1 W., W.M.

JACKSON COUNTY, OREGON

FOR

ELDON HUGIE

SURVEY BY L.R. SMITH EAGLE POINT, ORE.



20 21 1/4 Cor.

N0°04'19"W
990.07'

Fd. 5/8" I. Pin Exp. 2"

N0°46'51"W
330.14'

RS 5632

1/16 Cor. N89°43'24"W

990.87'

N89°43'24"W

1/16 Cor.

Fd. 5/8" I. Pin Flush

342.65'

BT's
8" W. Oak
Brs. N4°W 24'
10" W. Oak
Brs. N88°E 12.2'

LEGEND

- SET 5/8" X 24" IRON PIN
 - ⊙ Fd. 5/8" IRON PIN Co. R/W
 - ⊙ Fd. JACKSON Co. BRASS CAP & ACCESSORIES
- SCALE: 1" = 200' DATE: FEB. 6, 1984
BASIS OF BEARING RS 6165

**** RECEIVED ****

Date 2/14/84 By JK

This survey Consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY SURVEYOR

RS 6165

N0°14'58"W
1320.20'

DRIVE

N8°30'30"E

60'

687.42'

RIVER

L=413.02'
Δ=3°43'51"

RS 6972

ROGUE

N40°14'21"E

350.92'

1/16 Cor. N89°49'02"W

490.62'

N89°49'02"W

845.08'

20 21
29 28

Fd. 1/2" Pipe Flush

RS 6205

RED
PROFESSIONAL
LAND SURVEYOR

Lloyd R. Smith

OREGON
JULY 16, 1982
LLOYD R. SMITH
2011

0986

34 1W 20

Survey Narrative to Comply With O.R.S. 209.250

Survey For: Eldon Hugie
P.O. Box 1235
Shady Cove, Oregon

Location: Township 34 South, Range 1 West, Section 20

Basis of Bearing: Filed Survey No. 6165

Purpose: To monument property corners as indicated on the accompanying map.

Procedure: A closed traverse was surveyed, tying the existing corners found. The one-sixteenth corner and related property corners were then set.

Equipment Used: 20" Kern Theodolite, Lietz Red 1-A

Surveyed By: Lloyd R. Smith
404 Bigham Rd.
Eagle Point, Oregon
February 6, 1984

