



SURVEY NARRATIVE TO COMPLY WITH  
PARAGRAPH 209:250 OREGON REVISED STATUTES

Survey For: Mrs. Madeline Poole  
1731 Mill Creek Drive  
Prospect, Cr. 97540

Location: Northeast One-quarter Section 11, Township  
33 South, Range 2 East, Willamette Meridian  
Jackson County, Oregon


Basis of Bearing: North-South centerline of Section 11 as  
established by the B.L.M. survey.

Purpose: To establish the boundaries of that parcel of  
land described within Volume 570, Page 6 of the  
official records of Jackson County and a portion  
of the parcel situated to the West.

Procedure: Performed a closed traverse tying the North,  
East and Center one-quarter corners and the  
Northeast section corner. From this control  
I computed the position of the Southeast  
corner of the Northwest one-quarter of the  
Northeast one-quarter said point being the  
point of begining for the tract described  
within Volume 570, Page 6. This survey is  
shown within 'Detail A' on the attached map  
of survey. I then proceeded to layout the  
boundaries of the tract described within  
Volume 570, Page 6 along with the parcel of  
land situated to the West of said parcel.  
Those parcels are shown within 'Detail B'  
on the attached map of survey.

The mean centerline of Mill Creek Drive was  
tied at a distance Easterly and Westerly of  
the parcel and the bearing between said points  
utilized as the bearing of Mill Creek Drive.  
Monuments were set at a 30.00 foot offset  
and parallel to said centerline.

All controlling corner monuments recovered  
were found as described within the official  
B.L.M. record. All corner points were found  
in good condition with the exception of the  
Northeast section corner which was found to  
have all accessories removed or in a dead  
condition. I marked no new accessories at this  
corner point as the corner is situated near  
several residences.



February 25, 1984

HAROLD L. CENTER  
Registered Professional Land Surveyor  
Oregon Certificate No. 1071  
2604 David Lane  
Medford, Or. 97504

