

9953

### Map of Survey

Located in the southeast quarter of  
Section 16, Township 34 South, Range  
1 West of the Willamette Meridian,  
Jackson County, Oregon.

for

## BUS & PATTY MAXSON

BASIS OF BEARING: Filed survey no. 7252

○ Found 5/8" iron pin

● Set 5/8" x 24" iron pin w/ yellow plastic  
cap marked WEAVER L.S. 1679.

SCALE: 1" = 50'

DATE: APRIL 25, 1984

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Kurt C. Weaver*

OREGON  
JULY 14, 1978  
KURT C. WEAVER  
1679



Prepared by: Flatebo, Weaver & Assoc., Inc.  
P.O. Box 900  
Jacksonville, Oregon 97530

1.02 acres

N-S & Section 16 per filed survey no. 7252

(rec. N0°07'50"E 632.48)

632.68

N0°07'50"E

270.00

S55°44'19"E  
294.36

N0°02'03"W  
74.59

(rec.)  
N0°07'50"E  
29.61

S89°58'40"E 34.92

S89°58'27"W 208.96  
(rec. S89°59'25"W 209.00)

(rec. 35.00)

(rec. 384.00)

Fd. 3/4" iron pin C.S. 1/16 cor.  
Section 16 per filed survey no. 3633

**\*\* RECEIVED \*\***  
Date 5/3/84 By SK  
This survey consists of:  
— 1 sheet(s) Map  
— 1 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR

9953

34 1 N 16

Survey No. 9953

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250.

Survey for: Bus and Patty Maxson  
P.O. Box 1154  
Shady Cove, Oregon 97539

Location: Located in the southeast quarter of Section 16, Township 34 South, Range 1 West of the Willamette Meridian, Jackson County, Oregon.

Purpose: To monument the northerly line of the proposed parcel of land as shown on the accompanying map. A description of said parcel was also prepared.

Procedure: Monuments set by Charles Hurst, Professional Land Surveyor, on several separate filed surveys were recovered and tied. Monuments found along the line represented by Mr. Hurst as the north-south centerline of said Section 16 were utilized for the basis of bearing. The recovered monuments shown on the accompanying map were used to control the position of those monuments set.

Surveyed by: Flatebo, Weaver and Assoc., Inc.  
P.O. Box 900  
Jacksonville, Oregon 97530

Date: April 25, 1984

