

SURVEY NO. 9975

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: STATE OF OREGON AERONAUTICS DIVISION  
3040 25TH STREET S.E.  
SALEM, OR 97310

LOCATION: A PORTION OF THE NORTH ONE-HALF OF THE NORTHWEST ONE-QUARTER OF SECTION 8, TOWNSHIP 40 SOUTH, RANGE 4 EAST, WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON.

PURPOSE: TO SET MONUMENTS AT THE CORNERS OF THE PROPERTY OWNED BY THE STATE OF OREGON, KNOWN AS THE PINEHURST AIRPORT.

PROCEDURE: RAN A CLOSED TRAVERSE AROUND THE NORTH HALF OF SAID SECTION 8 TYING TO VARIOUS CORNERS USED AND SET DURING SURVEYS NO. 7200 AND 9364. SAID TRAVERSE WAS RUN WITH AN E.D.M. TOPCON GTS-2.

DURING THE 1970'S THE JACKSON COUNTY SURVEYOR'S OFFICE SEARCHED FOR THE NORTHEAST CORNER OF SECTION 8. THEY FOUND A PINE TREE LAYING ON THE GROUND WITH ORIGINAL SCRIBE ON IT. THEY COULD NOT FIND EVIDENCE OF WHERE SAID TREE HAD GROWN. THEREFORE, THE EXACT LOCATION OF SAID CORNER COULD NOT BE REESTABLISHED.

A NEW CORNER WAS SET FOR THE NORTHEAST CORNER OF SAID SECTION DURING SURVEY NO. 7200. BEFORE ACCEPTING THIS CORNER, ANOTHER SEARCH FOR THE ORIGINAL CORNER WAS MADE BY ME, AND RON FROST AND BOB MALOTE OF THE COUNTY SURVEYOR'S OFFICE. EVERY POSSIBLE COMBINATION OF BEARINGS AND DISTANCES FROM THE ORIGINAL NOTES AND FROM OLD K-TAGS FOUND IN THE AREA WERE USED TO FIND THE ORIGINAL STONE SET AT THE NORTHEAST CORNER OF SECTION 8. OLD MAPS OF THE AREA AND OTHER EVIDENCE INDICATED THAT THE CORNER FELL EAST OF AN EXISTING OLD DIRT ROAD. SEVERAL HOLES WERE DUG IN THE ROAD FILL LOOKING FOR SAID ORIGINAL STONE. NOTHING COULD BE FOUND. IT IS MY OPINION AND THE OPINION OF THE MEMBERS OF THE COUNTY SURVEYOR'S OFFICE THAT THE ORIGINAL CORNER WAS EAST OF SAID NEW CORNER BY APPROXIMATELY 60 FEET. HOWEVER, THERE WAS NOT ENOUGH ORIGINAL EVIDENCE EXISTING TO RE-ESTABLISH SAID CORNER IN ITS ORIGINAL POSITION.

A SEARCH WAS MADE FOR THE NORTH ONE-QUARTER CORNER OF SECTION 8 ALSO. IT WAS DETERMINED THAT THE ORIGINAL CORNER WAS WITHIN THE CLEARING DONE FOR THE PINEHURST AIRPORT. IN FACT, THE ORIGINAL CORNER WAS IN A WINDROW OF LARGE ROCKS AND STUMPS CREATED BY SAID CLEARING. I SET A 5/8 INCH IRON PIN AT THE

PROCEDURE: PROPORTIONED LOCATION OF SAID ONE-QUARTER  
(CONTINUED) CORNER FROM WHICH;

A 20" PINE BEARS N66°E 55.85 FEET SCRIBED,  
1/4 S 5 BT.

A 12" PINE BEARS S04°W 38.58 FEET SCRIBED,  
1/4 S 8 BT.

DATE: JUNE, 1984

