

NOTES:

- = Indicates Monument found
 - = Indicates 5/8" I. Rod with yellow plastic cap marked "TEMPLIN P.L.S. 1354" Set.
- Bearings are based on R.S. No. 6934

This Plat does not purport to show all recorded and unrecorded easements


**** RECEIVED ****
 Date 6/12/84 By SK
 This survey consists of:
 - 1 straight line
 - 1 curve
 RICHARD L. TEMPLIN JR.
 JACKSON COUNTY
 SURVEYOR

REGISTERED
 PROFESSIONAL
 SURVEYOR
 RICHARD L. TEMPLIN JR.
 JACKSON COUNTY
 1354

RICHARD L. TEMPLIN
 CONSULTING ENGINEER
 321 NW "A" Street Grants Pass, Oregon 476-7114

PLAT OF DEPENDENT RESURVEY
 LOCATED IN
 SE. 1/4 OF SW. 1/4 OF SECTION 15 AND THE
 NE. 1/4 OF NW. 1/4 OF SECTION 22, T36S, R.4W, W.M.
 JACKSON COUNTY, OR

Survey For: Kellenbeck Const. Co. Grants Pass, Ore
 Date 5-20-84
 Scale: 1" = 50'



RICHARD L. TEMPLIN
CONSULTING ENGINEER

9976

321 NORTHWEST A STREET
GRANTS PASS, OREGON 97526

TEL. (503) 476-7114

REGISTERED ENGINEER OREGON
REGISTERED LAND SURVEYOR
OREGON AND CALIFORNIA

May 16 , 1984

SURVEY NARRATIVE

LOCATION: SE 1/4 of SW 1/4 of Section 15 and NE 1/4 of NW 1/4 of Section 22, Township 36 South, Range 4 West, Willamette Meridian.

Survey For: Kellenbeck Construction Company, 830 N.E. Victoria, Grants Pass, Oregon.

Purpose: To retrace Survey No. 6934 executed by T. Flatebo R.E. 7971 in July 1977 and re-set controlling monuments destroyed by construction activities. Also, to establish a proposed land partition boundary in the Southerly part of Tax Lot No. 1100.

A search was made for monuments set as shown on Survey No. 6934 executed by T. Flatebo. Those monuments found are shown on the attached survey plat. A closed traverse survey was then made, which included all of the said found monuments.

Calculations were then made to determine the previous survey accuracy and possible relocation of said found monuments by persons unknown. All courses and distances shown on Survey Plat No. 6934 between said found monuments agreed very closely with calculated bearings and distances of this survey.

The destroyed corner monuments were then replaced with 5/8 inch diameter iron rods, 30 inches in length, set 30 inches in the ground marked "TEMPLIN PLS 1354" on Yellow Plastic Caps.

After replacing said missing monuments, distances were then measured between monuments for verification.

This survey was executed with a Wild T 16-ED. theodolite and a Mac 2 electronic measuring instrument.

All bearings are referred to the West Line of said parcel recorded on Survey No. 6934

** RECEIVED **
Date 6/12/84 By SK
This survey Consists of:
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Richard L. Templin, Jr.
OREGON
SEPTEMBER 23, 1977
RICHARD L. TEMPLIN, JR.
1354