

29

28

1/4 COR.
FD. IRON POST
WITH BRASS CAP

N 89° 30' 53" E 1311.47'
1237.56'

SET WITNESS
CORNER

WEST EVANS CREEK RD.

S 1° 22' 40" W

80.00'

FD. 5/8" I. ROD
PER CS 5029

159.95'

EVANS
CREEK

MAP

SHOWING A SURVEY IN THE SW 1/4 OF
SEC. 28, T. 35 S., R. 4 W., W. M., JACKSON
COUNTY, OREGON

APRIL 20, 1984 SCALE: 1" = 200'

SURVEYED FOR: RICHARD M. RUGGIERO
5201 WEST EVANS CREEK RD.
ROGUE RIVER, OREGON

SURVEYED BY: MAX H. HULL, SURVEYING
231 NW "B" STREET
GRANTS PASS, OREGON



*** RECEIVED ***
Date 6/11/84 By [Signature]
Number of copies of:
1 of [Signature]
1 of [Signature]
JACOB I. GENTRY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 11, 1969
MAX H. HULL
901

SURVEY NARRATIVE SEPARATE
MERIDIAN BASED ON CS 5029

- SET 5/8" X 30" IRON ROD
- FD. IRON MONUMENT AS NOTED

35 4 W 28

9979



MAX H. HULL Land Surveying

9979

Office 476-2425

231 N. W. 'B' Street Grants Pass, Oregon 97526

SURVEY NARRATIVE to comply with Paragraph 209.250, O.R.S.

DATE: April 20, 1984

FOR: Richard M. Ruggiero
5201 West Evans Creek Rd.
Rogue River, OR

PURPOSE: To survey and mark the South line of property located in the Southwest Quarter of the Northwest Quarter of Section 28, T-35-South, Range 4 West of the Willamette Meridian, Jackson County, Oregon.

PROCEDURE: Using monuments found per Survey No. 5029, I surveyed North $01^{\circ}22'40''$ East 80.00 feet; thence I surveyed South $89^{\circ}30'53''$ West 1311.47 feet to the West 1/4 corner at which point I found a B.L.M. brass cap with both bearing trees.

Meridian is based on Survey No. 5029.

