



18131

DESCRIPTION:-
 Beginning at a stone in center of county road, said point being on the north line of Donation Land Claim No 57 in Township 38 South of Range 1 West of Willamette Meridian and 2938 feet east of northwest corner of said claim, run thence east on said north line 3660 feet, thence N 0° 04' W 4085 feet, thence S 89° 57' E 2756.3 feet to center of county road, thence N 32° 01' W along center of road 1280 feet, thence N 89° 50' W 4353.2 feet, thence N 0° 02' W 1077 feet, thence S 89° 57' N 1287.4 feet to center of county road, thence S 0° 04' W 2479.5 feet to the point of beginning.

DEDICATION:-
 Know all men by these presents that I, W.T. York, am the trustee for the owners of the above described tract of land and that I have laid out the same into Lots and Roads as shown on the above plat and the same is a correct representation of said subdivision and I do hereby dedicate to the public for use as highways all roads shown hereon and do hereby designate the same as the MIDWAY TRACT.
 In witness whereof I have hereunto set my hand and seal this 16 day of January 1910.
 Done in the presence of
 W. M. Churchill, Witness.
 State of Oregon, S.S.
 County of Jackson

Personally appeared before me a notary public in and for the said state and county W.T. York of said state and county, personally known to me to be the above named, who executed the above instrument and who acknowledged to me that he did the same freely and voluntarily.

we, Osgood & Cummings, hereby certify that the above map was made from notes taken during an actual survey and that said map is a correct representation of said survey.

Subscribed and sworn to before me this 16 day of January 1910

Examined and approved this 28 day of January 1910.

For order of County Commissioners approving this plat see Page 13 Volume 178 of Commissioners Journal of Proceedings.

Filed March 25, 1910, W.R. Coleman, Clerk of Jackson County

MIDWAY TRACT.

Jan. 1910. Scale: 1 in = 300 ft.

Osgood & Cummings
 Civil Engineers,
 Medford, Oregon
 by A.T. Brown.

Filed Apr. 13, 1910
 at 9 o'clock A.M.
 R. T. Burnett
 Recorder

Traverse of Coleman Cr.	Traverse of Anderson Cr.
N 71° 55' E 500.0	N 24° 53' W 202.3
N 64° 02' E 501.8	N 50° 21' E 24.5
N 65° 17' E 91.3	N 6° 49' W 200.1
N 65° 14' E 254.7	N 66° 39' E 236.2
N 29° 29' E 112.4	N 1° 43' W 411.4
	N 8° 00' E 242.4
	N 3° 57' E 300.8