



# WOODVILLE CEMETERY

ROGUE RIVER, JACKSON COUNTY, OREGON.

PART OF SE 1/4 OF SECTION 15 T. 36. S. R. 4 W. W. M.

Scale 1 inch = 300 feet.

Surveyed March 1925

by C. Z. Boyden

Deputy Co. Surveyor.

**DESCRIPTION.**

Beginning at a 2 inch iron pipe 36 inches long 1/2 foot below surface of the ground, said point of beginning bears N 0° 40' W 20.00 feet from an iron pin at the 1/4 corner common to Sections 15 and 22 T. 36 S. R. 4 W. W. M. Thence N 0° 40' W 275.68 feet to a 2 inch iron pipe 36 inches long 1/2 foot below the surface of the ground. Thence S 89° 20' W 147.5 feet to 1/4 inch iron pipe. Thence N 0° 40' W 295.02 feet to a 1/4 inch iron pipe. Thence N 89° 20' E 295.02 feet to a 3/4 inch iron pipe. Thence S 0° 40' E 570.70 feet to a 2 inch iron pipe. Thence S 89° 20' W 147.5 feet to the point of beginning.

**DEDICATION.**

Know all Men by these Presents that the Woodville Cemetery Association is owner of the above described tract of land that we E. STEVENS, CHAS HATCH and W. H. MILTON are duly elected and qualified TRUSTEES of the said association, that we have platted the above tract into Blocks, Streets and Alleys, that the plat is a true representation of said tract, and that we do hereby designate the same as WOODVILLE CEMETERY of ROGUE RIVER, OREGON and dedicate to the Public use forever all Streets and Alleys hereon shown.

In Witness whereof we have hereunto set our hands and seals this 11th day of April 1925

Done in the presence of

*Harold Wiley* Witness  
*Harold Wiley* Witness

*E. Stevens* Chairman of Trustees  
*Chas. Hatch*



State of Oregon }  
 County of Jackson } Personally appeared before me a Notary Public in and for said State and County E. STEVENS, CHAS HATCH and W. H. MILTON, known to me to be the above named Trustees who executed the above instrument and acknowledged to me that they signed the same as their free and voluntary act and deed for the uses and purposes thereon mentioned, the day and year above written.

My Commission expires 29th day of March 1929 *Boyd* Notary Public for Oregon.

I, C. Z. Boyden hereby certify that the above plat was made from notes taken during an actual survey on the ground during March 1925 and that said plat is a correct representation of same.

Subscribed to and sworn to before me this 11th day of April 1925. *Boyd* Notary Public for Oregon. My Commission expires 29 day of March 1929

Examined and approved this 4 day of May 1925 *J. B. Clement* County Assessor  
 Filed for record this 6 day of May 1925 and duly recorded in Volume 5 Page 22 Book of Plats  
*Geo. Allen* Co. Comm.

Examined and recommended for approval of County *Delicia Stevens* County Clerk

*J. G. Cowgill* County Surveyor  
*Ralph G. Jennings* Sheriff