LAND OF MANY OAKS, ADDITION 3

LOCATED IN SECTION 33, T. 35 S., R. 2 W., JACKSON COUNTY, OREGON

SCALE |" = 200'

of the original plat filed with the County Clerk.

DEDICATION

KNOW ALL MEN BY THESE PRESENTS that we, Charles W. Duggan and Rosellen Duggan are the owners in fee simple of the lands hereon described, and that we have subdivided the same into lots, blocks and streets as shown hereon, and the number and size of the lots and the length of all lines are plainly set forth, and that this is a correct representation of the said subdivsion, and we do hereby dedicate to the public for public use all streets and paths as shown hereon, and we do hereby designate said subdivision as, LAND OF MANY OAKS ADDITION 3 IN WITNESS WHEREOF we have set our hands and seals this 10 day of aug. 1965. Rosellen Duggan STATE OF OREGON SS A4645T, 10TH AD 1965 Personally appeared the above named Charles W. Duggan and Rosellen Duggan and acknowledged the foregoing instrument to be thier voluntary act and deed. Before me asy machintook Notary Public for Oregon My Commission expires the 22 day of AUGUST 1968 Examined and approved by the Jackson County Planning Commission in regular session this 17th day of SEPTEMBER 1965 Examined and approved this 15th day of September 1965 All taxes paid in full to date this the 15 day of Man the 15th day of SEPT. 1965 For Order of the County Court approving this plat see Volume. Page ____of County Commissioner's Journal of Proceedings.

Examined and recommended for approval by the County Court this By Deputy 635552 Filed for record this the 22 day of september 1965 at 10:21 O'clock A.M., and recorded in Volume 10 of Plats at Page 17 of Records of Jackson County. By Deputy

SURVEYOR'S CERTIFICATE STATE OF OREGON SS County of Jackson We, the undersigned hereby join in the foregoing Plat and dedication. I, Verlyn Thomas, a duly registered Surveyor of the State of Oregon, being first duly sworn, do hereby certify that I have correctly surveyed and marked with proper monuments as provided by law the tract of land hereon shown, and the said plat is a correct representation of the same, and the following is an accurate description of the boundary lines; Beginning at a concrete monument with metal tablet at the center Quarter Corner of Section 33, Township 35 South, Range 2 West of the Willamette Meridian, Jackson County, Oregon, said monument being N 0° 34'50"W, 2637.92 feet from the Quarter Corner on the South line of said Section 33; thence N 0°34'50"W, 644.34 feet; thence S 89°54'20"W, 33.24 feet; thence N 37°03'20"W, 1497.55 feet to the southerly line of State Highway No. 234; thence along said highway Billie L. Cloud right of way line on a spiral curve left (the chord of which curve bears S 43°15'40"W, 106.36 feet) a distance of 106.36 feet to a point 70.0 feet S 46°50'E from Engineers Station PS 395+71.72: thence S 43° 10'W along said southerly right of way line STATE OF OREGON SS 1071.80 feet; thence N 46°50' W along the highway right of way line 20.00 feet to a point 50,00 feet \$ 46° 50'E from Engineer Station 385+00; County of Jackson thence \$ 43° 10' W 47.95 feet to the northeast corner of Lot 7, Block 3 Land of Many Oaks, (a recorded Subdivision); thence August 25 AD 1965 S 46° 54' 20" E, (Record S 46° 48' 30" E) along the northeasterly boundary of Lots 6 and 7, Black 3, said subdivision, 588.85 feet; thence Personally appeared the aboved named and acknowledged S 0°28'30' E, (Record'S 0° 31'30" E), 47.81 feet to the northwest corner the foregoing instrument to be their voluntary act and of Land of Many Oaks, Addition 2 (a recorded Subdivision); thence deed. Before me along the north boundary of said Addition 2, N 89°28'30" E, 680.00 feet; thence along the easterly boundary of said Notary Public for Oregon Addition 2, S 0° 31' 30"E, 512.75 feet; thence S 89° 48' 15" E, 680.62 feet to the point of beginning. My Commission expires the // day of October Surveyor Subscribed and sworn to before me this 10 day of AUGUST 1965. Notary Public for Oregon My Commonission expires the 22 day of 946457 1968 N 89° 54' 20" E 33.24 27.81 399.90 314.64 680.00 S 89°28'30"W 414.54 LAND OF MANY OAKS ADDITION 2 RECISTERED OREGON N 89° 27' 20" E LAND SURVEYER 16 erlyn Momas MAY 13, 1000 Note: Meridian based on Land of Many Oaks, S 89° 28' 10"E Addition 2. VERLYN THOMAS 17 5/8"x 30" Iron Rods set flush at all corners. INITIAL POINT S 89° 48' 15" E 680.62 Center 1/4 Corner Section 33 I hereby certify that this tracing is an exact copy

263 N 0°

South 1/4 Corner Section 33